

DREXAN™ HeatTracer

PipeGuard™ CMH-PAU

Constant Wattage Metallic-Sheathed Pre-assembled Heating Cable Unit



Drexan HeatTracer is pleased to offer any number of Pre-Assembled Unit (PAU) configurations of PipeGuard CMH its innovative and cost-saving Constant-Wattage, Metallic-Sheathed, Cut-to-Length, High-Temperature Heating Cables.

While normally shipped to site in standard 500-foot reels ready for fabrication and termination in the field or modular-yard installation by contractor personnel, further savings in time, labour, quality and reliability are possible if you take advantage of our factory-assembled, pre-tested, and tagged units.

Pictured above is one example especially valuable for installation on such piping stubs as Drains, Vents, Gauges, and other Instruments...or on any other short piping lengths which are normally very difficult or impossible to handle economically with series-circuit Mineral Insulated Cables. This is especially valuable on projects which comprise dozens or perhaps hundreds of similar elements.

The PipeGuard CMH-PAU's are available in standard heated-lengths of 1 – 10 feet at 120V, 208V, 240V, and 277V at standard wattage outputs from 5 – 30 watts per foot. (Custom lengths are also available. Please consult your local Technical Representative.)

They can be delivered to the jobsite as pictured above with 2 terminated ends each ready for entry into a single Junction Box or with one end terminated as shown above for connection to power in a Junction Box or a Quick Connection device and the other end with a pre-terminated low-profile end seal installed.

Right Product, Right Place, Right Price™

Heating Cables

www.drexanheattracer.com

Tech Line:
1-800-663-6873

Drexan™ HeatTracer Division
© 2011 Drexan Energy Systems

Doc. No.HD111208-1